



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-13-00272

OWNER'S NAME: JUMP

DATE: 12/4/2015

TYPE: Framing and mechanical

TIME STARTED: 10:34 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 17-18-05040-0020

	1. Gas at 25#-ok
	2. Air handler in living space cannot supply air to garage. Disconnect ducts to garage
	3. Fireplace ok.
	4. Install FSK paper behind fireplace for protection of spray foam insulation
	5. Obtain engineering for furnace in attic trusses
	6. Stamped truss sheets not on site
	7. H2.5 clips on girder trusses
	8. Drain line for coil in attic not installed. Emergency drain line or "condensate cop" to be installed on furnace emergency drain pan. See by final
	9. Verify UL listing of attic spray foam to conform to R316.6

INSTRUCTIONS: Complete above, corrections can be seen at insulation. Check truss bracing at insulation

NEXT INSPECTION: Insulation

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

_____ jessica.contratto@co.kittitas.wa.us

• **INSPECTION REQUEST LINE:** www.co.kittitas.wa.us/cds/request.asp or 509-962-7694 •

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506