



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00203

OWNER'S NAME: STRINGFELLOW

DATE: 9/16/2015

TYPE: Framing and mechanical

TIME STARTED: 11:17 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 20-17-32057-0002

	1. outlookers to be at 24" oc per plan. Currently 2x4 48" oc
	2. gable brace every 48" per detail A/A7
	3. post down in overframing exceeding 4" height
	4. have insulation collar and chimney rough installed by insulation inspection
	5. strap top plate to glulam at kitchen entryway
	6. tempered window at soaker tub
	7. email stamped revision for header change at kitchen
	8. combustion air to be verified by final for woodstove
	9. mechanical ok

INSTRUCTIONS: ok to insulate, see corrections then.

NEXT INSPECTION: insulation

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

_____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

• INSPECTION REQUEST LINE: www.co.kittitas.wa.us/cds/request.asp or 509-962-7694 •

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506