



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

## INSPECTION REPORT

PERMIT NUMBER: BP-16-00249

OWNER'S NAME: COVEY

DATE: 4/26/2017

TYPE: Framing

TIME STARTED: 11:12 AM

INSPECTOR: Justin Bennett

MAP NUMBER: 19-15-08051-0004

1. Trusses D2D & D4D have been modified @ bearing ends for outlookers - provide manufacturer Ok
2. Truss B2 does not have clips @ bearing on porch beam
3. Provide 4x6 post @ master window per review notes (3) locations
4. Provide framing @ both ends of window wall per dwg - (3) kings & (2) trimmers
5. Verify LSTA straps @ ridge beam per dwg
6. Provide H2.5 @ Rafters per dwg
7. Provide positive connection @ post to beam connection for side porch
8. Provide strap @ sunroom beam to top plate connection (2) locations
9. Fireplace and B Vent not installed
10. NOTE: S10 has a note referring to updated Roof Framing dwgs - not on site
11. Attic Access needed in Utility Rm Hall

INSTRUCTIONS: Complete above

NEXT INSPECTION: Re-Inspection

RE-INSPECTION FEE DUE?



NO



YES

\$ \_\_\_\_\_

**IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION**

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL  
ADDRESS: justin.bennett @co.kittitas.wa.us

**INSPECTION REQUEST LINE: 509-962-7694**

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506