



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

## INSPECTION REPORT

PERMIT NUMBER: BP-16-00501

OWNER'S NAME: COSTA

DATE: 12/2/2016

TYPE: Framing

TIME STARTED: 2:07 PM

INSPECTOR: Justin Bennett

MAP NUMBER: 18-19-13000-0001

1. Range vent has aluminum tape - not insulated
2. Supply duct main still not insulated
3. Porch soffits are enclosed - need to verify truss installation
4. Provide truss manufacturers approval to notch gable trusses for outlookers
5. L&I inspection not complete
6. Install RBC @ 24" OC per detail 1/A4 at eaves
7. Need to verify detail 7/A4 @ soffits
8. Header @ slider is 4x8 - 4x10 per dwgs
9. Header not per plan for West window in Great Rm
10. Provide strap @ top plate for slider
11. Porch beams and connections covered - need to verify

INSTRUCTIONS: Complete corrections above/Re-Inspection

NEXT INSPECTION: Re-Inspection

RE-INSPECTION FEE DUE?



NO



YES

\$ \_\_\_\_\_

**IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION**

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL  
ADDRESS: justin.bennett @co.kittitas.wa.us

**INSPECTION REQUEST LINE: 509-962-7694**

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506