



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-16-00546

OWNER'S NAME: BUILDWORX

DATE: 6/6/2017

TYPE: Framing

TIME STARTED: 9:22 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 22-11-04053-0904

1. Exhaust duct ok
2. Gas piping not completed
3. Verify Fire Marshal has approved burial line to building
4. Detail 6/S5.1 at closet walls upstairs not complete. HTC4 clip required for movement. A35 clips installed
5. Detail 3/S5.1 at bedrooms dividing wall not complete. HTC4 clip at every rafter
6. All exposed Glulams not treated per plan. Verify means of weather protection
7. Main Floor::::
8. Detail 10/S4.2 at kitchen shearwall. Blocking where joists parallel and A35 clips per detail
9. Detail 7/S4.2 at closet walls. Blocking where joists parallel and A35 clips per detail
10. Detail 4/S4.2 at bedrooms front wall. Blocking where joists parallel and A35 clips per detail
11. Garage Level::::

INSTRUCTIONS: Complete above

NEXT INSPECTION: RE-inspection

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: _____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-16-00546

OWNER'S NAME: BUILDWORX

DATE: 6/6/2017

TYPE: Framing

TIME STARTED: 9:22 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 22-11-04053-0904

Page 2

12. CSMT14 straps at panels on bedroom cantilever. Also detail 2/S4.2 not complete. Wrap stap under beam

13. Detail 11/S4.2 not completed at bedroom cantilever. Blocking at 48" per detail

14. Verify deck ledger attachment requirements at back decks. None on plan due to no ledger in framing detail

15. Verify requirements and detail for GWB draftstops at 10' vertically in party wall. Wall studs do not line up across party wall.

INSTRUCTIONS: Complete above

NEXT INSPECTION: RE-inspection

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: _____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506