



KITITITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-16-00695

OWNER'S NAME: RICHTER

DATE: 6/9/2017

TYPE: Framing

TIME STARTED: 1:45 PM

INSPECTOR: Justin Bennett

MAP NUMBER: 21-16-31020-0007

1. All headers require (1) Jack & (2) Kings typical unless noted otherwise
2. Verify MST & CS strapping @ top of beam to top plate connection - Multiple locations
3. Front porch soffit enclosed - need to verify ledger attachment and framing
4. Rear Porch not complete
5. Roof sheathing edge blocking not complete - clouded on page 5
6. Ledger for kitchen/utility ceiling attached with nails - provide engineer attachment detail
7. Range Vent not installed in kitchen
8. EF in bathroom & utility room not ducted/terminated
9. Gas @ 5# - needs to be 15#/15 mins

INSTRUCTIONS: Complete above

NEXT INSPECTION: Re-Inspection

RE-INSPECTION FEE DUE? NO YES \$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: justin.bennett @co.kittitas.wa.us

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506