

From: [Amanda Grindle](#)
To: [Zach Torrance-Smith](#)
Cc: [Jamey Ayling](#); [Chace Pedersen](#); [Bradley Gasawski](#); schroej@wsdot.wa.gov; [Dempsey, Tim](#); [Eric Martin](#); [Erik Hogeberg](#)
Subject: RE: PF-24-00001 WSDOT Bullfrog Maintenance Facility - Transmittal of Comments
Date: Thursday, February 15, 2024 3:30:21 PM

CAUTION: This email originated from outside the Kittitas County network. Do not click links, open attachments, fulfill requests, or follow guidance unless you recognize the sender and have verified the content is safe.

Good afternoon Zach,

Below in **bold** are our responses to the questions/comments posed by the Department of Ecology for the WSDOT Bullfrog Maintenance Facility Fuel System Replacement project. Can you please pass these along?

- Due to the volume of oil stored onsite, a SPCC plan is probably required (40 CFR 112.7) if one has not been written already. Please refer to those regulations for any requirements that need to be met in order to have aboveground storage tanks.
Yes, the facility will have an updated SPCC Plan prepared for the site.
- Is the fuel line to the dispenser double walled? If not, WSDOT may consider using double walled piping to allow any leaks to leak from the damaged fuel line into of the sumps for easier detection by onsite staff.
Yes, the fuel line is double-walled. We will be using OPW Flexworks piping that is a coaxial 1.5" fuel piping.
- Are the storage tanks double walled? What type of interspatial leak detection do these tanks have?
Yes, the storage tanks are double-walled; they are Regal UL 2085-rated Fireguard tanks; interspatial leak detection will be performed by a Veeder-Root 7984380-430 sensor.

Also, in response to both the DAHCP and Colville Tribe's comments, an Inadvertent Discovery Plan (IDP) will be prepared for the site.

Please let me know if there are any additional questions or information required.

Thanks!

Amanda Grindle | **Saybr Contractors, Inc.**
Direct 253.533.2382 | **Office** 253.531.2144 Ext. 103 | **Cell** 253.882.4546
www.saybr.com | agrindle@saybr.com

From: Zach Torrance-Smith <zach.torrancesmith@co.kittitas.wa.us>
Sent: Tuesday, February 13, 2024 9:12 AM
To: schroej@wsdot.wa.gov; Amanda Grindle <agrindle@saybr.com>
Cc: Jamey Ayling <jamey.ayling@co.kittitas.wa.us>; Chace Pedersen <chace.pedersen@co.kittitas.wa.us>; Bradley Gasawski <bradley.gasawski@co.kittitas.wa.us>
Subject: PF-24-00001 WSDOT Bullfrog Maintenance Facility - Transmittal of Comments

Good morning,

Attached you will find correspondence regarding PF-24-00001 WSDOT Bullfrog Maintenance Facility. A physical copy of the correspondence will also be placed in the mail.

Please contact me with any questions or concerns.

Zach Torrance-Smith

Planner I

Kittitas County Community Development Services

411 N. Ruby St., Suite 2

Ellensburg, WA 98926

P: 509-962-7079

zach.torrancesmith@co.kittitas.wa.us

If this is about a Public Records request, please go to <http://www.co.kittitas.wa.us/request/default.aspx> and fill out a request for public records through the GovQA portal.

The information transmitted by this email is intended only for the person or entity to which it is addressed. This email may contain confidential and/or privileged material. If you are not the intended recipient of this message, be aware that any use, review, retransmission, distribution, or reproduction is strictly prohibited. If you received this in error, please contact the sender immediately and delete the material from all devices.
message id: 38eb45916c6dcbdac24bb8719d004a14