



KITTITAS VALLEY FIRE & RESCUE

400 E Mt View Ave • Ellensburg WA 98926 • (509) 933-7241 • Fax (509) 933-7245 • prevention@kvfr.org

KVFR Prevention Short Plat Comments

Project: Morazz Short Plat
Permit#: SP-22-00001
Date: 04/07/2022

I have reviewed the Short Pat and associated documents for the listed project and/or construction for Kittitas County Fire District 2 (KVFR). The Fire District has no code enforcement authority so my input is, from a fire department response and operational basis.

Comments:

- Fire apparatus access roads exceeding 150' shall be provided with a temporary or permanent turnaround meeting the requirement 2018 IFC Appendix D.
- Fire apparatus access roads shall not exceed 10% in grade. This is especially critical in our valley's climate.
- The IFC Appendix D requires the road be a minimum of 20' wide and capable of supporting an imposed load of at least 75,000 lbs.
- Road turning radius required under IFC Appendix D are a minimum of 23' inside and 45' outside.

Thank you,

Joe Delvo
Fire Prevention Captain
Fire Investigator, IAAI-FIT
Kittitas Valley Fire & Rescue
400 East Mountain View Ave.
Ellensburg, WA
Phone: 509-933-7241
Cell: 509-856-4455
Fax: 509-933-7245
prevention@kvfr.org