



U.S. Fish &amp; Wildlife Service

## National Wetlands Inventory

Branch of Resource and Mapping Support

Enter Classification code:  (Example: **L1UB1Hx**)

For geographically specific information\* (optional), please enter a State code:  (Example: **TX** for Texas)

Description for code **PEMC**:

**P** System **PALUSTRINE**: The Palustrine System includes all nontidal wetlands dominated by trees, shrubs, emergents, mosses or lichens, and all such wetlands that occur in tidal areas where salinity due to ocean derived salts is below 0.5 ppt. Wetlands lacking such vegetation are also included if they exhibit all of the following characteristics: 1. are less than 8 hectares ( 20 acres ); 2. do not have an active wave-formed or bedrock shoreline feature; 3. have at low water a depth less than 2 meters (6.6 feet) in the deepest part of the basin; 4. have a salinity due to ocean-derived salts of less than 0.5 ppt.

Subsystem :

**EM** Class **EMERGENT**: Characterized by erect, rooted, herbaceous hydrophytes, excluding mosses and lichens. This vegetation is present for most of the growing season in most years. These wetlands are usually dominated by perennial plants.

Subclass :

Modifier(s):

**C** WATER REGIME **Seasonally Flooded**: Surface water is present for extended periods especially early in the growing season, but is absent by the end of the growing season in most years. The water table after flooding ceases is variable, extending from saturated to the surface to a water table well below the ground surface.