



KITTITAS COUNTY DEPARTMENT OF PUBLIC WORKS

411 N. RUBY STREET, SUITE 1 ELLENSBURG, WA 98926

(509) 962-7523

HANSON, CLAIRE

Permit No.: **AC-14-00128**

Application Date: July 10, 2014

Issue Date: July 24, 2014

Application Status: final

Expiration Date: **January 06, 2015**

July 24, 2014

Dear HANSON, CLAIRE;

Your access/address onto Naneum Road
has been conditionally approved by Kittitas County with the following conditions:

APPLICATION INFORMATION

Application for: Address Permit Access Permit

Assessor Map No.: 18-19-16051-0001

Access Requested for: COMMERCIAL LOT Desired Width of Driveway: _____ Feet

Nearest Intersection or Address: Approx. 175 feet to northern neighboring property.

NEW ADDRESS

Your New Address is: Naneum Road

City: _____ Zip: _____

ACCESS REQUIREMENTS

ALL REQUIREMENTS OF PERMIT TO BE COMPLETED PRIOR TO ISSUANCE OF:

BUILDING PERMIT OCCUPANCY PERMIT

PAVED APRON REQUIRED - WSDOT DESIGN STANDARDS

PRIVATE ROAD CERTIFICATION REQUIRED

CULVERT REQUIRED

Minimum Culvert Diameter: _____ Inches

Minimum Beveled End Length: _____ Feet

Total Culvert Length: _____ Feet

CULVERT LENGTH CALCULATION

Length = $W + 8H + 2$ (All Measurements in Feet)

W = Width of driveway

8 = (Constant) Angle of side slopes (2x4:1)

H = Height of culvert + depth of fill above culvert

2 = (Constant) One-foot pipe extension beyond fill ends

- Pipe to be bedded on a minimum of 4" of 5/8 gravel or equivalent, with a minimum cover of _____ inches.
- Culverts shall be constructed of new galvanized steel or new plastic HDPE pipe.
- Maintain a 4:1 slope from the driveway surface to the top of culvert.
- Bevels on culvert to be cut at a 4:1 slope.

INSPECTION OF COMPLETED ACCESS REQUIRED CALL 509-962-7523 TO SCHEDULE YOUR INSPECTION

Other Requirements/Comments:

Applicant has bonded for Improvements to Access. No requirements at this time.

FILE

Reviewed By: KELLY BACON

Date: 07/24/2014

Approved By: KELLY BACON

Date: 07/24/2014