



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00215 OWNER'S NAME: WEST
DATE: 1/14/2016 TYPE: Framing
TIME STARTED: 11:14 AM INSPECTOR: Jessica Contratto
MAP NUMBER: 20-14-24050-0517

	1. Stamped truss sheets not on site
	2. A35 clips at gables per shearwall schedule and red pen on page A7
	3. Strap top plate to header over slider at kitchen to porch
	4. detail for outlookers shows inverted inverted LUS26 on interior end per 11/D5
	5. Post down between floors in stairwell at multiple trimmer locations
	6. Beam changes at rear patio ok
	7. Skewed hangers for trusses above furnace? Provide attachment clarification from manufacturer
	8. Gas at 9#, not sufficient for test
	9. CS16 x 48" straps over decorative beams. Bubbled page A5
	10. Post down under header carrying beam at poder room door by office
	11. Complete upper draftstop at fireplace. Solid filled cavity of insulation will provide draftstop in stud bays at lower draftstop

INSTRUCTIONS: Complete above, re-inspect

NEXT INSPECTION: re-inspect

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

_____ jessica.contratto@co.kittitas.wa.us

• INSPECTION REQUEST LINE: www.co.kittitas.wa.us/cds/request.asp or 509-962-7694 •

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00215

OWNER'S NAME: WEST

DATE: 1/14/2016

TYPE: Framing

TIME STARTED: 11:14 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 20-14-24050-0517

	Page 2
	12. Provide FSK paper behind fireplace
	13. Address top plate breaks at decorative truss bottom chords along fireplace wall
	14. Correct cut out shearwall in kitchen
	15. Shearwall omitted in stairwell. Obtain revision

INSTRUCTIONS: Complete above, re-inspect

NEXT INSPECTION: re-inspect

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

_____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

• INSPECTION REQUEST LINE: www.co.kittitas.wa.us/cds/request.asp or 509-962-7694 •

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506