



KITITITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

# INSPECTION REPORT

PERMIT NUMBER: BP-15-00364                      OWNER'S NAME: REIMER  
DATE: 10/1/2015                                      TYPE: Framing  
TIME STARTED: 12:42 PM                      INSPECTOR: Jeremy Haberman  
MAP NUMBER: 20-15-19051-0038

1. Shear Corrections Remain. Engineering Required.
2. Fireplace Rough In OK.
3. Truss Bracing Missing On A2, B4, C2, C3 and C4
4. 4x10 Header Required at Guest Bath and Stairwell Window.
5. Posts Under Girder & Rafter Bearing at Exterior Wall of Loft.
6. Clips Required from Rafters to Top Plate at Entry Wall.
7. Detail 5 on D4 Not Complete.
8. Header Required at Pantry Entrance.
9. Repair Severed Stud at Range Vent.

**INSTRUCTIONS:** Make Corrections Above. OK to Insulate. Leave Access at Cathedral Cielings for Correction Verification.

**NEXT INSPECTION:** Insulation.

RE-INSPECTION FEE DUE?     NO     YES    \$ \_\_\_\_\_  
**IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION**

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

\_\_\_\_\_ jeremy.haberman @co.kittitas.wa.us

• **INSPECTION REQUEST LINE:** [www.co.kittitas.wa.us/cds/request.asp](http://www.co.kittitas.wa.us/cds/request.asp) or 509-962-7694 •  
411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506