

Copy KMZ file and paste it here:



Wanapum boat
launch restroom rep



Scope of work

Project:

Under fill a 15' section of an ADA ramp that leads up a hill to a restroom. This area had a washout from a waterline break. The slab was undermined and is being held up by its hand railing. The plan is to form the sides of the walkway and pour cement under. Once cured, hire a company to come and slab jack this section back to existing grade. Also slab jack one other section back into place to maintain accurate grade. Material will have to be imported to fill the sides along the walkway where it was washed away. Once filled large cobble rock will be placed back over to match existing. About 10 yards of fill material and 5 yards of rock will be hauled in and placed with about 6 yards of cement poured.

Excavation:

No excavation should be needed. Form steaks will need to be driven into the ground to set forms for cement.

Vegetation:

No vegetation will need to be disturbed.

Water's Edge:

Shoreline it 35' from work zone to the water's edge.

Staging:

Staging materials will be in the parking lot above the last water bar in the parking lot so all runoffs will be directed into the grass swell. Cement washouts will be contained in a wash pit built above ground and disposed of properly after.

ADA:

Yes, this is an ADA restroom with no usable access, and we will have to close two ADA parking stalls to access the work zone.



