

Voelker Engineering
193 N Shugart Flats Rd
Leavenworth, WA 98826
425-417-1122

JOB Black Horse 96004.1
SHEET NO. 1 OF 2
CALCULATED BY _____ DATE 4.16.24
CHECKED BY _____ DATE _____
SCALE _____

Rank Extruder moment.

Check Loads to Figs:

$$F_{h1} = 20 \times \frac{23}{2} + 80 \times \frac{12}{2} \times 1.25 = 380 \text{ k}$$

$$F_{h2} = 20 \times \frac{10.5}{2} = 105 \text{ k}$$

$$OTM = 380 \times 11 + 105 \times 5.5 = 4757 \text{ k-ft}$$

$$DL = 4.5 \times 4 \times 130 = 2.4 \text{ k}$$

RECEIVED
APR 17 2024

Kittitas County CDS

4/16/24



EXPIRES 9/21/25

Sign Footing

Axial Load			Moment		
P =	2.40	kip	M =	4.80	k-ft
Footing Input			Conc. f'c	2500	psi
Length	3.50	ft	Soil Hgt	1.00	ft
Width	3.50	ft	Soil wt	125	pcf
Thickness	10.00	in			
Column Size			Ftg DL	1.53	kips
Width1 =	6.00	in	Soil Wgt	1.53	kips
Width2 =	6.00	in			

Footing Properties

A =	12.3	ft ²	I =	12.5	ft ⁴
S =	7.1	ft ³			

Stability

Sum of Dead Loads	5.46	kips			
Resisting Moment	9.56	k-ft	S.F. =	1.99	
Soil Pressure					
ecc =	0.88	ft	<=	Outside Kern	
P/A =	0.45	ksf			
OTM Pressure =	1.19	ksf	Total =	1.19	ksf

Punching Shear

Width1 at critical section =	0.79	ft	Width2 =	0.79	
Factored bearing pressure =	0.67	ksf			
Bo =	38	in	Bo x D =	266	in ²
vu =	29	psi	Allowable vu =	170	psi

One-way Shear

Vu@ "D" =	3.82	kip	vu =	13.0	psi
			Allow Vu =	85.0	psi

Flexure

		Load Factor =	1.4		
Direction W1				Minimum steel required	
Mu =	6.7	(k-in)	.0018xAREA	4/3xAs	
Req'd As =	0.02	(in ²)	0.76	0.03	
Direction W2				Minimum steel required	
Mu =	21.5	k-in/ft	.0018xAREA	4/3xAs	
Req'd As =	0.07	(in ² /ft)	0.22	0.09	