

Govorship 20 N. 9. 13 East W. M. Washington.

۷

- Transcript of the field notes of the survey of the
West side lines of Sec. 6, in Township No. 20
North of the baseline of Orange Co., 13 East of
the Mill. Mer, in the State of Washington; - as
conveyed by A. H. Whittemore, U. S. Deputy Surveyor,
under his contract No. 529 with the U. S. Genl. Surv. of
the public lands of the United States in the State
of Washington; and said contract bearing date of
the 12th day of May of the year A. D. One
thousand eight hundred and ninety seven (1897).
From the cor. of Secs. N. E. 7, and 12, on the N. E. 1/4 of Th.
20 n. R. 13 E., W. 29 M., which cor. is described as follows:
" 300 ft. ascent above the last brook, and across a brush pass,
8 ft. long, 3 in. sq., and 2 ft. in the ground, for the cor. of
Secs. N. E. 7, and 12, marked 1/2 20 n. S. 6. on the N. E. face;
R. 13 E. S. 7, on the S. E. face; R. 12 E. S. 12, on the S. W. face;
S. 1. on the N. W. face, with 5 matches on the S. edge,
and broach on the N. edge, ang. from which back
about 18 in. in dia., hrs. 1/2 20 n. 1/2 S. E. S. 1. S. 2.
Spire 36 " " " 7.60³ E. 15 " " " 7.20 n. R. 13 E. S. 6. " "
" 16 " " " 2.74⁴ E. 51 " " " " " " " " S. 7. " "
" 36 " " " 0.264 W. 14 " " " 7.20 n. R. 12 E. S. 12 " "
Sept. 13. 1897
I enclose from said cor. True
North on a true merid. Sec. line 6. - Over unto land
and tree heavy timber and dense undergrowth, continue ascent
5. 00 a rock cliff, 50 ft. high, hrs. E. and the
6. 00 top of mtn spur, 250 ft. ascent, slopes N. E., and begin
to descend a m. w. slope.
§ 2.07 To the center of tract of the N.C.R.R., on tan hrs. 7.86¹² W.,
and S. 86¹² E., point of intersection R. R. R. Sta., 89 95 + s.,
20.00 feet a hemlock, hast 8 ft. long, 3 in. sq., 2 ft. in the ground, for the 1/4
sec. cor., marked 1/4 S. 1. on the N. face, 7.60³ E. on the E. face, 0.264 W. on the
spire, 20 in. in dia., hrs. 7.43³ E. 32 cts. dist., marked 1/4 S. 1. S. 7.
slouch, 5 " " " 0.52³ E. 3 " " " 4. S. 6. " "
Sept. 14. at 9 a.m., set off 47¹/₂ in the lat. asc. E. 30° 09' on the decl. asc.
42.00 an old cabin, hrs. E. 250 ft. dist.
53.00 to the bottom of descent, 700 ft. and enter bottom land.

Transcript of the field notes of the survey of the
length of the last closing mile of the 5th dist. Rail
R. R. No. R. 11 E., with R. 12 E., and its intersection;

the closing cor. of Rps. 20 N. Rps. 11 and 12 East of the
will run in the State of Washington; surveyed by
A. S. Ruth, U. S. Deputy Surveyor, under his contract No. 574.
bearing date of the 23d day of April, A. D. 1901.

The Stand. cor. of Rps. 21 N. Rps. 11 and 12 E., N. W. cor.

From the Stand. cor. of Secs. 35 & 36, R. 21 N., R. 11 E., W. M., from

Cloudy, impassable to date and obs. on Polaris; July 13, 1901).

" S. 89° 58' E., on second S. of Sec. 36."

80.00 " 360 ft. from the second, and roofed, above the St. cor.; 1
mile west; Det. post, sp. t. long, brn. sq., and sp. t. in the
ground, further Stand. cor. of Rps. 21 N., Rps. 11 and 12 E., W. M.,
marked S. C. S. 21 N., on the N. face; R. 12 E., S. 31, on the S. face, S.
R. 11 E., S. 31, on the W. face; with 6 grooves on the N. c. & W.
faces, and from which post

Rps. 32 N. and 11, Rps. 21 N. R. 12 E., S. 31, R. S.

" " 48 " " " 21 N. R. 11 E., S. 31, R. S.

July 13, 1901.

The closing cor. of Rps. 20 N., Rps. 11 and 12 E., N. W. M.; From the
cor. of Secs. 16, 17, and 12, on the E. bdy. of Rps. 20 N., R. 11 E., W. M., from
(July 23, 1901; at 7 h. 10 m. a.m. L. m.t., Left off 47° 15' N. on the
Lat. arc, and 20° 10' M. on the decl. arc, and determine a
true mer. with the solar at the cor. of Secs. 16, 17, and 12).
North lat. Secs. 1 and 2; ascend then heavy timber.
Lat. the 5th Stand. Dist. at a point 5.05 ch. W. of
the Stand. cor. of Rps. 21 N., Rps. 11 and 12 E., W. M., and
sets sp. t. post, brn. sq., sp. t. long, and sp. t. in the ground,
for the closing cor. of Secs. 1 and 2, marked C. C. 120 N.,
on the S. faces; R. 12 E., S. 6, on the E. face, and R. 11 E. S. 1
on the W. faces; with 6 grooves on the S. E. & W.
faces, and from which post

Rps. 10 N. and 11, Rps. 20 N. R. 12 E., S. 31, R. S.

" 20 " " " S. 6 1/2 E., 22 " " " S. 20 N., R. 11 E., S. 31, R. S.

July 23, 1901.

Saturday 21 M. in 12 C.M. in Washington.

۷

Transcript of the field notes of the survey of the land lot.
Sections 15 and 22, in Township No. 21 North of the
Baseline of Range No. 12 East of the Meridian, in the
State of Washington, as surveyed by C. S. Anthon, my Deputy
Surveyor, under his contract No. 587, bearing date of
the 15th day of April, of the year A.D. 1902.

From the sea. of Sec. 14, 15, 22 and 3; which cor. is described as follows: " Sets about 3 ft. long, thin &g; and 1 1/2 ft. in the ground; for the sea of Secs 14, 15, 22, & 3, mated 9.217, Dec. 14, on the N.E. face; R. 12 E., S. 23, on the S.E. face; S. 22, on the S.W. face, and S. 15, on the N.W. face, with 2 notches on the edges, and 3 notches on the dredge; from which last 3 cor. mated, no. 67 on W. 30, N. 80, dist. mated 9.217. Apr. 2 E., S. 15, S. 2.

Hencefrom said son James

\$0.00 Set a post for the temple 4 Dec. cor.

1. Intersect the body of the sp. at a point below. S. of the cor. of osca. 15°-22°, which is described as follows:

3 ft. long, 4 in. sq., alt. 2 ft. in the ground, for the rear of Deco.

1222, worn 1, 2, 17, S. W. on Merriam's place, June 11, 1912.

W. 89° S. 58' E., on a tame line, bet. Secs. 15 and 22.
Over-level land and thru dense timber and underbrush
Is a creek, 2 ft. wide, course N. E.

21.00 To the Dogqualme Road, which lies N. 65° W. and S. 65° E.
22.71 Detachment of fract. 3 ft. long, thin, sq., and 2 1/2 in. in the ground,
for the 4 dec. cor., wanted 2 d. 1/2 on the rt. face, and 22. on the

S. face; and from which part
about 16 ins. in dia., two S. 4700 ft., 26 lbs. dist., measured by S. G. T.
Sphere, 12 " " " 21.5700 ft. 19 " " " " " "

79.70
To a wagon road, bearing N. 70° E. and S. 80° W.
84.71
To the cor. of Secs. 14, 15, 22, 23.

Soil of hemlock, fir, and pine, with enough of the same.
May 10, 1902.