



Kittitas County
PUBLIC WORKS

**KITTITAS CO CDS
RECEIVED
10/24/2023**

411 N. Ruby Street, Suite 1 Ellensburg, WA 98926

ACCESS/ADDRESS PERMIT

STATE OF WASH (DNR)
PO BOX 47014 C/O CONSERV REC & TRANSACTION DIV
OLYMPIA, WA 98504-7014

8/8/2023

Permit No: **AA-23-00076**
Application Date: 8/8/2023
Issue Date: 8/8/2023
Application Status: ISSUED
Expiration Date: **8/7/2024**

Your access/address onto 1701 WEST FORK TEANAWAY RD-TRAILHEAD PARKING LOT has been conditionally approved by Kittitas County with the following conditions.

APPLICATION INFORMATION

Assessor Map Number: 20-15-01000-0001

Assessor Parcel Number: 129234

Access Requested For:

Desired Width of Driveway: 40 Feet

NEW ADDRESS

Your New Address is: 1701 WEST FORK TEANAWAY RD-
TRAILHEAD PARKING LOT

City: CLE ELUM Zip: 98922

ACCESS REQUIREMENTS PRIOR TO BUILDING PERMIT

- PAVED APRON REQUIRED - WSDOT DESIGNED STANDARDS
- PRIVATE ROAD CERTIFICATE REQUIRED
- APPROACH (FIRST 20 FEET) TO BE CONSTRUCTED TO THE ATTACHED ROAD ACCESS DESIGN
 - Construct apron (20 feet) with no more than 6% grade
 - Compacted gravel surface layer required
 - 10 foot turning radius on apron
 - Side slopes off of apron not to exceed a 4:1 slope

CULVERT LENGTH CALCULATION

Length = $W+8H+2$ (All Measurements in Feet)

W = Width of Driveway
8 = (Constant) Angle of side slopes (2X4:1)
H = Height of culvert + depth of fill above culvert
2 = (Constant) One-foot pipe extension beyond fill ends

- ACCESS IS FROM PRIVATE ROAD. CULVERT DESIGN WILL BE AT OWNERS DISCRETION TO MAINTAIN DRAINAGE AS NEEDED.

- CULVERT REQUIRED

Minimum Culvert Diameter: Inches

Minimum Beveled End Length: Feet


Total Culvert Length: Feet

**CALL FOR INSPECTION
WHEN DRIVEWAY IS
COMPLETED 509-962-7523**

- Pipe to be bedded on a minimum of 4" of 5/8 gravel or equivalent, with a minimum cover of
- Culverts shall be constructed of new galvanized steel or new plastic HDPE pipe.
- Maintain a 4:1 slope from the driveway surface to the top of culvert.
- Bevels on culvert to be cut at a 4:1 slope.
- Please see design sheet attached.

ACCESS TO BE COMPLETED AND INSPECTED PRIOR TO THE ISSUANCE OF A BUILDING PERMIT
CALL (509) 962-7523 TO SCHEDULE YOUR INSPECTION

DRIVEWAY REQUIREMENTS PRIOR TO OCCUPANCY PERMIT



Kittitas County
PUBLIC WORKS

411 N. Ruby Street, Suite 1 Ellensburg, WA 98926

ACCESS/ADDRESS PERMIT

- Side slope off driveway surface layer not to exceed a 2:1 slope
- Driveway not to exceed 10% grade.
- Blue address plate to be installed at driveway prior to inspection.
- Permit is for a trailhead parking lot

DRIVEWAY REQUIREMENTS TO BE COMPLETED AND INSPECTED PRIOR TO THE ISSUANCE OF OCCUPANCY
CALL (509) 962-7523 TO SCHEDULE YOUR INSPECTION

Reviewed By: Jackie Sharp

Date: 08/08/2023

Approved By: _____

Date: