



MATERIAL

TIMBER			IRON		CONCRETE	
NO. PIECES	DIMENSIONS	F.B.M.	NAILS	BOLTS	1-7 MIX.	CEMENT SAG
4	2'x6'-20'	80	60#-60#	12-1/2"x9		
2	2'x4'-20'	27	2"-40#		18 1/2#	18...
15	4'x12'-18'	1080	2"-1/2 CUT WASH: 4			
29	4'x12'-16'	1856				
2	4'x4'-18'	32				
	TOTAL	3075				

PLAN
 OF
BRIDGE OVER CASCADE CANAL
 NEAR KITTITAS WASHINGTON
 OFFICE OF COUNTY ENGINEER
 MARCH 9, 1912
 SCALE 1/2"=1'